

### **OPERATION SHEET**

#### **TRENCHER**

## SAFETY/RISK/HAZARD ASSESSMENT

#### **PLANT INFORMATION**

NHG Ref/Part No. LoaKtre

Plant ID:

**Plant Name:** 

**Potential Noise Level in Db:** 

Required hearing protection class: 2

Operator Competency: Plant Licence Not Required

It is the hirer's responsibility to ensure that all operators are

competent.

Please refer to the User Guide and Operators Manual for

detailed Operating Instructions





#### **RISK ASSESSMENT INFORMATION**

Page 1 of 4 WNCS0101APAL00360

#### Potential Hazard(s)

#### **Crush injury**

Risk Level Medium

Control Measures Keep unauthorised persons away from site

Establish a 4 meter exclusion zone around the local working area and ensure no person other than the operator, enters this zone whilst the machines engine is

running.

Do not place any article or body part under the trencher at any time.

#### **Fault to underground services**

Risk Level Medium

Control Measures Check with local authorities and land owners about the presence of underground

services within the prospective working area prior to commencement of work.

Ensure excavations are located a minimum of 2 meters away from ANY

underground service.

# Please refer to the User Guide and Operators Manual for detailed Operating Instructions

The safety information contained in this assessment is general information only and should not be relied upon as a substitute for professional advice or tuition, which the hirer should seek before operating.