

## Site Buildings

### RISK ASSESSMENT INFORMATION

#### Potential Hazard(s)

##### Crush injury

Risk Level Medium

Control Measures Ensure all persons are clear of building during loading, unloading & setup.

Building should be placed on a level compacted base, away from any water collection point or pathway (natural or planned) which could undermine foundation on which building is placed, making it unstable.

Do not allow children to play in or around building.

Ensure all contents and connections are disconnected and secured prior to moving.

##### Electrocution

Risk Level Medium

Control Measures Ensure all power leads and electrical appliances are kept dry and away from water sources.

Do not touch electrical components or equipment with wet/damp hands.

Check any leads/connections for damage or deterioration and do not use if damage detected.

##### Water Hazards

Risk Level Medium

Control Measures Keep door closed when not in use and supervise children during use.

##### Burn Hazard

Risk Level Medium

Control Measures Carefully check water temperature prior to entering shower or placing any body part under running water.

Keep all body parts away from hot components (urn, hot water service, etc).