



Traffic Lights Pre-Start Procedure

Please follow instructions below.

If in doubt, please contact Northern Hire Group for further instruction.

Please refer to Towing - Trailer data sheet for safe towing procedure

1. Inspect all moving parts, joints and locking pins for excessive wear, for correct adjustment and for vandalism and/or damage prior to towing or raising the board.
2. Check the lantern doors are securely fastened.
3. Ensure lantern mountings are secure.
4. Ensure signal lanterns are covered when in the travel position as exposure to direct sunlight may damage the lantern lens.
5. Check batteries and wires for loose or damaged connections.
6. Check battery levels.

Please report all faults, signs of wear/damage, leaks, or any other maintenance issue immediately to Northern Hire Group Pty Ltd personnel.

Do not consent to, or attempt any repair without authorisation from Northern Hire Group Pty Ltd.